

QUOTATION FOR BUILDING WORK

Ref our advertisement published in the Jag Bani (Patiala Bani) on 19 Feb 2024.

Ser No	Description of Item	Unit	Rate
1	Supply & fixing HDF Laminated floor tounge/ grooved strips 4' x 6" x 10mm over existing hard surface of approved shade including edge fixing. Make - Action TESA	Sqft	
2	Supply & fixing perforated gypsum board/tile 2' x 2' x 12mm over wall or false ceiling for acoustic affect. Make Gyproc	Sqft	½
3	Supply & fixing 2' x 2' grid of 2½" x 1½" partal wood frame to fix perforated board including Anti Termite Treatment to the wooden members.	Rft	
4	Supply & filling of sound absorb wool of best quality in above grid below perforated board/tile	Sqft	
5	Supply & laying of vitrified double charged 1000 x 1000mm x 10mm floor tile of any shade over 25 - 40mm thick CM 1:4 mortor bed including epoxy filling joints of matching shade. Make - Orientbell	Sqft	
6	Supply & fixing glazed wall tiles 1' x 1½' in dado with cement mortor 1:2 and filling joints with epoxy of matching shade. Make Orientbell.	Sqft	
7	Supply & fixing anti-skit 1' x 1' floor tiles laid on CM 1:4 mortor bed including epoxy filling of joints	Sqft	
8	Supply & fixing of gypsum false ceiling 2' x 2' x 8mm tile over GI frame. Make - Gypro	Sqft	
9	Supply & fixing of 2' x 2' LED lights 36w for false ceiling. Make - Havells Model - Octane	Each	
10	Supply & fixing of PVC wall paneling of approved shade. Make - Décor	Sqft	
11	Commercial Plywood 6mm, 9mm, 12mm, 25mm. Make - Duro	Sqft	
12	Supply & fabrication Aluminum frame work (powder coated) for sliding door, window shutters. Including glazing Make - Mahavir	Kg	
13	Supply of LED Flood Lights 50w. Make Havells	Each	

Note : Quantity shall be intimated at the time of order

(Signature of
supplier)