

**BOQ FOR REPAIR TO CEILING PLASTER OF GIRLS BOARDING HOUSE AT  
YADAVINDRA PUBLIC SCHOOL, PATIALA**

Ser No	Nature of work	AU	Qty	Rate	Amount
1	Removal of cement plaster from soffit of roof slab including disposal of malba from second floor to designated place in the campus	Sqft	3200		
2	Provision and laying shot concrete 1 : 1 1/2 : 3, 20mm thick with 3mm crushed stone aggregate	Sqft	3200		

Ref

Advertisement published in the Jag Bani (Patiala Bani) on 15 Aug 2024

**BOQ FOR MS FRAME TO FIX XPM JALI FOR SHOT CONCRETE OF GIRLS BOARDING  
YADAVINDRA PUBLIC SCHOOL, PATIALA**

Ser No	Nature of work	AU	Qty	Rate	Amount
1	Removal of existing false ceiling frame and gypsum tiles 2' x 2'	Sqft	3200		
2	Refixing of false ceiling	Sqft	3200		
3	Provision and fixing of false ceiling gyp tile 2' x 2' over GI frame	Sqft	200		
4	Provision and fixing of XPM jali including welding work	Sqft	3200		
5	Provision and fixing MS sq pipe 50 x 50mm	Kg	1250		
6	Removal of wiring, ceiling fan, lights and refitting	Job	1		

Ref

Advertisement published in the Jag Bani (Patiala Bani) on 15 Aug 2024