

YADAVINDRA PUBLIC SCHOOL, PATIALA
BOQ : CONSTRUCTION OF CARPENTRY SHOP

Name of Firm :

Date

Ser No	Nature of work	AU	Qty	Rate	Amount
1	Excavation in any soil of foundation	Cft	200		
2	Returning and filling of excavated earth in foundation and floor	Cft	600		
3	PCC 1:4:8 in foundation	Cft	180		
4	Brick work in CM 1:6 in foundation upto plinth level	Cft	200		
5	Brick work in CM 1:6 in superstructure	Cft	150		
6	RCC Lintel band 6" thick in CM 1:2:4 including shuttering	Cft	25		
7	Cement plaster in CM 1:6, 20mm thick	Sqft	2200		
8	PCC flooring in CM 1:2:4, 50mm thick	Sqft	400		
9	DPC 40mm thick in CM 1:2:4	Sqft	95		
10	Providing and fixing MS window frame & shutter size 3' x 4'	Nos	4		
11	Providing and fixing MS door frame & shutter size 7' x 4'	Nos	1		
12	Providing and hoisting steel structure for roof including vertical post	Kg	200		
13	Providing and fixing ACC sheets in roofing	Sqft	650		
14	Providing and fixing ACC ridge	Rft	36		
15	Providing and applying wall putty including preparation of surface	Sqft	2200		
16	Providing and applying water based primer	Sqft	2200		
17	Providing and applying Red Oxide over steel surface	Sqft	250		
18	Providing and applying enamel paint over steel surface	Sqft	250		
19	Providing and applying OBD two coats	Sqft	2200		
20	Providing and fixing MS Bars for reinforcement	Kg	50		
				Total	

Signatures with stamp

NOTE: Advertisement being published in the Jag Bani (Patiala Bani) on 07 Aug 24.