

**BOQ FOR RENOVATION OF TOILETS OF INFIRMARY AT
YADAVINDRA PUBLIC SCHOOL, PATIALA**

Ser No	Nature of work	AU	Qty	Rate	Amount
	<u>CIVIL WORK</u>				
1	Dismantling of BB work built in cement mortar and removal of malba (CSR 8.39)	CuM	1		
2	Dismantling of terrazo/PCC flooring and dado and removal of malba (CSR 8.40)	Sqm	110		
3	Scraping of cement plaster and removing malba (CSR 8.31 (c))	Sqm	40		
4	Removal of sanitary fittings such as WC seats, wash basins (CSR 30.88)	LS	1		
5	Providing and laying anti-skid ceramic floor tiles 300 x 300x10mm (CSR 14.72)	Sqm	21		
6	Grouting joints of tiles having joint 3mm thick using epoxy grout (CSR 14.120)	Sqm	110		
7	Providing and fixing glazed wall tiles 1' x 1'-6" (CSR 14.127)	Sqm	90		
8	Providng and fixing Aluminium frame and door shutter (CSR 17.47(b))	Kg	40		
9	Providing and fixing 12mm thick prelaminated particle board in panelling (CSR 17.46(i))	Sqm	4		
10	Providing and fixing glazing 5mm thick (CSR 17.47(i))	Sqm	3		
11	Cement plaster in CM 1:6	Sqm	40		
12	Supply & applying wall putty	Sqm	80		
13	Supply & applying two coat of OBD over one coat of primer	Sqm	80		

Ser No	Nature of work	AU	Qty	Rate	Amount
	<u>PUBLIC HEALTH WORK</u>				
14	Providing and fixing in position Chinaware EWC with P or S trap of approved make with 10 ltr chinaware matching flush cistern and seat cover complete in all respect	Nos	3		
15	Providing and fixing in position best Indian make white ordinary wash basin including CP-32 mm waste and one CP Brass tap/pillar cock 550 x 400mm (CSR 30.19)	Nos	3		
16	Providing and fixing 32mm dia CPVC waste pipe embeded in wall upto floor level (CSR 30.19)	Nos	3		
17	Providing and fixing in position best Indian make bevelled edge 5mm thick mirror mounted on walls with cromium plate studs size as peer site (CSR 30.61)	Sqm	3		
18	Supply & fixing urinval flat back with spreader & waste pipe	Nos	1		
19	Supply & fixing CP long nose bib cock 15mm	Nos	6		
20	Providing and fixing CP-100mm dia grating (CSR 30.80)	Nos	10		
21	Providing and fixing in position 15mm dia bib cock of best quality (CSR 30.65)	Nos	9		
22	Providing and laying CPVC pipes laid in floor or mounted/embeded in walls including cost of specials (CSR 20.19)	RM	25		
23	Providing and fixing CP overhead shower (round/square) with shower arm 1' (CSR 30.56)	Nos	3		
24	Providing and fixing paper holder fixed to walls (CSR 30.57)	Nos	3		
25	Providing and fixing towel ring CP 150 - 200 mm dia (CSR 30.58 (b))	Nos	3		
26	Providing and fixing CP brass acrylic shelf size 560x130mm (CSR 30.59)	Nos	6		

Ser No	Nature of work	AU	Qty	Rate	Amount
27	Providing and fixing in position AI/CP khunti with 3 pegs (CSR 30.63)	Nos	3		
28	Supply & fixing CP soap dish	Nos	3		
29	Supply & fixing 15mm CP Jet	Nos	3		
30	Providing and fixing CP Brass extension pieces 25mm to 50mm long (CSR 30.64)	Nos	5		
31	Providing and fixing Stopcock/Angle valve concealed 15mm dia (CSR 30.66)	Nos	7		
32	Providing and fixing in position PVC flexible tube connection 15mm x 300 to 450mm with nuts (CSR 30.72)	Nos	3		
	<u>ELECTRICAL WORK</u>				
33	Provision and fixing exhaust fans Havells make 12"	Nos	3		
34	Provision and fixing LED light 10w including wiring Havells	Nos	3		

NOTE: Advertisement being published in the Jag Bani (Patiala Bani) on 07 Aug 24.